OFFICE OF THE PRESIDENT, MANDYA TOWN MUNICIPAL COUNCIL, MANDYA.

Tender Notification dated 23rd February 1940.

1. Notice is hereby given that sealed tenders will be received at the Office of the President, Mandya Town Municipality, Mandya, upto 3 P.M. on 25th March 1940, for constructing a Slaughter House in Mandya Town. An approximate estimate of quantities is given below. These quantities are only approximate. The work should be completed by the end of June 1940.

2. The plans, detailed estimates and conditions may be seen at the Town Municipal Office at Mandya, on all working days between 11 A.M. and 5 P.M.

3. Tenders should be submitted in the prescribed form the Public Works Department and should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury Chellan for earnest money of Rs. 250 paid to treasury to the head of deposit and be superscribed "Tender for constructing Slaughter House at Mandya," in default of which the tender will be rejected.

5. The final acceptance of the tender will rest with the Municipal Council, Mandya, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever, for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the notice board in the Town Municipal Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department, or those fixed by the Municipal Council after working out data.

11. In all matters not specifically provided for and in all maters of dispute about rates, quantities, measurements, quality, of works, etc., and in all disputes of any kind, the decision of the Municipal Council will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. The quality of the materials used and the work should be as per specification.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills of the contractor and the same repaid after the due fulfilment of the contract.

Abstract estimate for constructing Slaughter House at Mandya Town.

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
			Rs. a. p.		
1	Earthwork excavation, etc. ...	Cyds.	0 4 0	99	
2	Stone Jelly concrete in lime mortar (1—3).	Cft.	0 4 0	459	
3	Size stone in clay for foundations and basement.	,,	0 3 3	2,646	
4	Superstructure with brick in clay ...	,,	0 3 3	3,363	
5	Burnt brick in mortar ...	,,	0 4 0	323	
6	Providing and fixing 6″ Stone Slabs with rough dressings, etc., complete on doors, windows, ventilators, below girders, steps, etc.	Sft.	0 4 0	204	
7	Providing and fixing teakwood doors with 3″ and 4″ frame battered with shutters 1″ thick with hinges, iron fittings complete.	,,	1 8 0	149	
8	Providing and fixing gate 6′×3′ with expanded metal shutters including frame iron fitting, etc., complete with painting.	,,	1 0 0	18	
9 (a)	Providing and fixing Teakwood windows with battered shutters including iron fittings and bars $\frac{3}{4}$″ thick, etc., complete.	,,	1 10 0	96	

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
			Rs. a. p.		
9 (*b*)	Providing and fixing teakwood windows with battered shutters including iron fittings and bars ¾" thick with fixing brass wire gauge in the airing room for fly-proof as per design.	S.ft.	1 14 0	27	
10	Providing, fixing R. C. Ventilators as per design.	,,	0 8 0	48	
11	Providing and fixing R. C. Ventilators with brass wire meshing per fly-proof arrangements in aring room.	,,	0 12 0	50	
12	Providing, hoisting and fixing R. S. Girders of 4"/7"/161 lbs. and tangle iron for hanging purposes including bolts, nuts, wherever necessary with painting, etc.	Total in cwts.	14 0 0	21·41	
13	Providing and fixing R. C. slab of 6" thick over girder of opening between slaughter and skinning and over big window.	S.ft.	0 14 0	63	
14	Roofing with reinforced cement concrete 5" thick and 2 courses of flat tiles over surki concrete 3" thick including cement plastering below and ½" chunam plastering the above complete.	Sqr.	60 0 0	14·85	
15	Providing and fixing R. C. parapet wall 2½' high 4½" thick as per design for verandah.	S.ft.	0 8 0	64	
16	Constructing plain parapet wall over roofing with brick-in-mortar 1½' high 9" thick including, plastering, etc., as per design with front view also alround.	R.ft.	0 6 0	207	
17	Providing and fixing expanded metal of 1" mesh over 2" angle iron framing including painting complete.	S.ft.	0 4 0	550	
18	Cement mortar plastering (1:3) of ½" thick interior portion alround.	Sqr.	8 0 0	45·97	
19	Lime mortar plastering ½" thick interior	,,	3 0 0	39·62	
20	White or colour washing 2 coats as per lime mortor plastering as per item No. 19.	,,	0 5 0	39·62	
21	Flooring with 1½" cement concrete (1:2:4) over 3" lime and jelly concrete 1 : 3 and ½" cement mortar plastering 1 : 3 etc., complete.	,,	22 0 0	18·07	
22	Cement pointing to basement	,,	4 0 0	4·00	
23	Chocolate painting 2 coats ...	,,	3 0 0	5·43	
24	Providing and fixing to walls R. C. Slab sun shades with 3' by a required length and 4" thick including brackets etc., wherever necessary complete as per design.	S.ft.	0 7 0	282	
25	Providing and fixing iron hooks for hanging purpose with 1" thick rod and 4 feet length fixed to tangle iron across including bolts, nuts and brackets and painting also complete by four rows of 2'—5" apart as per plan.	Nos.	2 0 0	36	

No.	Items of work	Unit	Rate	Quantity	Rate to be tendered
			Rs. a. p.		
26	Constructing, gutting platform with brick in chunam mortar cement plastering and with teakwood shutter as per design.	No.	15 0 0	1	
27	Constructing flood-pool cistern with brick in mortar and cement plastering complete	,,	5 0 0	1	
	and providing with zinc bucket ...	,,		1	
28	Constructing 4″ stoneware half pipe (glazed) drain over a bed of cement concrete with neat finishing, etc., complete.	R.ft.	0 8 0	38	
29	Boxing girders with cement mortar and plastering, etc., complete over pillars.	,,	0 5 0	111	
30	Filling earth to basement with watering and bricking, etc., complete.	C.yd.	0 2 0	51	
31	Providing and fixing 6″×4″ thick jelly heep in cement concrete alround complete.	Nos. 2	5 8 0	2	
32	Constructing inspecting chamber 18″×18″ with burnt brick in cement mortar 9″ thick cement concrete bed with ½″ cement plastering covered with C. D. air-tight frame and lid with earthwork excavation to required depth, etc., complete.	1	15 0 0	1	
33	Supplying and laying and jointing 4″ S. W. Pipe of approved quality with hemp caulking and cement mortar jointing including earthwork excavation refilling trench, etc. complete.	R.ft.	0 14 0	65	
34	Constructing septic tank 6′×3½×5′ with 1′ cement concrete bed brick in cement mortar for walls alround 9″ thick cement plastering inside ½″ covering with burnt stone slab 6″ thick including providing C. I. man-whole cover 21″ diameter frame with steps, etc., complete as per design with earthwork excavation and screening arrangements.	1	100 0 0	1	
35	Constructing soakage pit to required dimension earthwork excavation and filling with boulders of different sizes and covering in top with small jelly including providing loose S. W. Pipe complete as per design.	1	30 0 0	1	
36	Constructing ventilating shaft with 4″ diameter boiler iron tube pipe with cavel bends, etc., 8′ high fixed in roof with necessary supports, etc., complete as per design.	1	15 0 0	1	
37	Clearing site and levelling ground ...	Lump-sum	10 0 0	...	
38	Unforseen ...	Do	30 0 0	...	

Total Rupees.....

B. BEERAPPA,
President.